

[← Back to the previous page](#)


Three numbering systems on one line

Every Wenhui station has two numbers. On the southern half they run in opposite directions, and the northern half uses a different series again — because the line was built as two projects and a station was added to one of them late.

BR WENHU LINE [/RAIL/METRO/LINES/WENHU-LINE/] 文湖線			
LINE Wenhui [/rail/metro/lines/wenhui-line/] ^[1]	OPERATING CODES BR01 — BR24 ^[1]	ENGINEERING SERIES Two — one of 13, one of 11 ^[1]	WHICH WAY THEY RUN Opposite, on the Muzha [/rail/metro/stations/br02/] section ^[1]
WHERE THEY INVERT BR01 — BR13 ^[1]	WHERE THEY AGREE BR14 — BR24 ^[1]		

Two numbers for every station

The signs carry one — BR01 to BR24, the operating code, the one passengers use. The construction drawings carried another. On the southern half the drawings counted from the opposite end, so **BR01 Taipei Zoo was drawing number BR13**, and **BR13 Songshan Airport was drawing number BR1**. Below, each station on the left is joined to its own drawing number on the right. Where the two systems disagree the joins cross; where they agree they run straight across.



Every station on the Wenhua Line [\[/rail/metro/lines/wenhua-line/\]](/rail/metro/lines/wenhua-line/) has two numbers ^[1]. One is on the signs. The other is on the drawings, and almost nobody outside the project has seen it.

The diagram above puts them side by side. Above the rule, the two orders run in opposite directions and the connecting lines cross. Below it, they agree — and the numbers are not even in the same series.

The operating code

BR01 to **BR24**, south to north, the codes on every platform sign, map and train announcement^[1]. They arrived late. The line opened in 1996^[1]; the line number and colour were assigned on 11 October 2014 and the two-letter station code in October 2016^[2]. **For its first eighteen years this railway had a name and no code**^[2].

The engineering number

DORTS lists a second number against every station in its own project table^[1]: the 工程編號, the number the station carried while it was being built.

On the Muzha [/rail/metro/stations/br02/] section it runs **north to south**, the reverse of the operating code:

OPERATING	STATION	ENGINEERING
BR01	Taipei Zoo [/rail/metro/stations/br01/]	BR13
BR02	Muzha	BR12
BR03	Wanfang Community [/rail/metro/stations/br03/]	BR11
BR04	Wanfang Hospital [/rail/metro/stations/br04/]	BR10
BR05	Xinhai [/rail/metro/stations/br05/]	BR9
BR06	Linguang [/rail/metro/stations/br06/]	BR8
BR07	Liuzhangli [/rail/metro/stations/br07/]	BR7
BR08	Technology Building [/rail/metro/stations/br08/]	BR6
BR09	Daan	BR5
BR10	Zhongxiao Fuxing	BR4
BR11	Nanjing Fuxing	BR3
BR12	Zhongshan Junior High School [/rail/metro/stations/br12/]	BR2

OPERATING	STATION	ENGINEERING
BR13	Songshan Airport [/rail/metro/stations/br13/]	BR1

Thirteen stations, and the two numbers sum to fourteen at every one of them^[1].

The third series

The Neihu [\[/rail/metro/stations/br19/\]](/rail/metro/stations/br19/) stations do not continue the BR series. They start again at B1:

OPERATING	STATION	ENGINEERING
BR14	Dazhi [/rail/metro/stations/br14/]	B1
BR15	Jiannan Rd. [/rail/metro/stations/br15/]	B2
BR16	Xihu [/rail/metro/stations/br16/]	B3
BR17	Gangqian [/rail/metro/stations/br17/]	B4
BR18	Wende [/rail/metro/stations/br18/]	B5
BR19	Neihu	B6
BR20	Dahu Park [/rail/metro/stations/br20/]	B7
BR21	Huzhou [/rail/metro/stations/br21/]	B8
BR22	Donghu [/rail/metro/stations/br22/]	B9
BR23	Nangang Software Park [/rail/metro/stations/br23/]	B10
BR24	Taipei [/rail/thsx/stations/taipei/] Nangang Exhibition Center	B11

Eleven stations, running the same way as the operating codes, in a series of their own. That is what a separate design and contract package looks like from the outside.

The station that does not fit

Look at the boundary. The Neihu section is BR13 to BR24 — twelve stations. The B series has eleven. BR13 Songshan Airport is a Neihu-section station carrying a Muzha-section number^[1].

The chronology says why it might be. Songshan Airport was not in the original scheme: MOTC directed a study on serving the airport directly in February 2000, the Executive Yuan agreed in principle on 1 August 2001, and the funding was approved on 4 January 2002^[1]. By then the Neihu section's B series had been allocated to the stations that already existed on paper.

A station added to a project after its numbers were handed out has to go somewhere. This one went into the other series, at its head.

That last step is this site reading the table, not DORTS explaining it. The addition date is the builder's; the inference about the numbering is ours, and it is offered as a reading rather than a fact. What the table shows without interpretation is that the number is in the wrong series for the section the station is in.

Why any of it matters

Taipei's network was not designed and then built. It was built project by project, each with its own budget, contractor, systems supplier and drawing set, and then operated as one railway afterwards. Almost every oddity on this site traces back to that — two incompatible fleets on one line, a depot in the wrong district for its name, station numbers that jump 29 places on the Zhonghe–Xinlu Line [\[/rail/metro/lines/zhonghe-xinlu-line/\]](/rail/metro/lines/zhonghe-xinlu-line/).

The numbering is the cleanest evidence of it, because it is the seam left visible in the paperwork. The signs were made to be read by passengers on a finished railway. The drawings were made by two teams, working outward from their own starting points, years apart.

Sources

Every number on this page is transcribed from DORTS's own station table for the 文山內湖線 project^[1]. The station registry carries the engineering number as a field, so the diagram, the tables and the station pages read the same values and cannot drift apart.

References

1 of 2 sources on this page is primary — published by the operator, the builder or government.

- 1** **Wenshan—Neihu Line** [\[https://www.dorts.gov.taipei/cp.aspx?n=DBAC040496EFAB94\]](https://www.dorts.gov.taipei/cp.aspx?n=DBAC040496EFAB94)
文山內湖線

PRIMARY

 Taipei City Government, Department of Rapid Transit Systems (DORTS)
accessed 2026-08-07
archived [\[https://web.archive.org/web/20260209210832/https://www.dorts.gov.taipei/cp.aspx?n=DBAC040496EFAB94\]](https://web.archive.org/web/20260209210832/https://www.dorts.gov.taipei/cp.aspx?n=DBAC040496EFAB94)
The builder's own station table, which is where the engineering numbers come from: it lists 工程編號 against 車站編號 for all twenty-four stations, together with addresses and exit counts. Every number on this page is transcribed from it. The same page also carries the Songshan Airport

station's chronology — MOTC directs a study in February 2000, the Executive Yuan agrees in principle on 1 August 2001, the Public Construction Commission approves the funding on 4 January 2002.

2 Wenhu line [<https://zh.wikipedia.org/zh-tw/文湖線>]

文湖線

SECONDARY 維基百科 (Chinese Wikipedia) accessed 2026-08-07

archived [<https://web.archive.org/web/20250714045049/https://zh.wikipedia.org/zh-tw/文湖線>]

Cited here only for the two dates the operating code arrived on — the line number and colour on 11 October 2014, the two-letter station code in October 2016. Neither is in DORTS's project record, which stops at the opening; a TRTC announcement would be the primary source and has not been found.

Last updated: 2026-08-07

An independent, non-commercial reference site. Not affiliated with any transit operator or government body in Taiwan. Line colours are the official values published by each operator through Taiwan MOTC's open data platform. **About this site.**

Station names, codes and sequence from TDX Transport Data eXchange, Ministry of Transportation and Communications, operators TRTC, NTMC, TYMC, and TMRT. Government open data. Retrieved 2026-08-24; source last updated 2016-11-23. The 12 Sanying station records absent from TDX are sourced directly to New Taipei Metro and government publications on their pages. Provenance.